

C.L. NORTH

C.L. North Pump Company

6820 Industrial Avenue  
El Paso, TX, 79915  
Phone # (915) 772-1469  
Fax # (915) 779-2658  
www.clnorth.com

Bill To: El Paso County Auditors Office  
El Paso County Auditors Office  
320 S.Campbell  
El Paso, TX 79901  
(915) 546-2040 ex 452

INSTRUCTIONS: REFERENCE REGION 19# 22-7434

FOR FABENS POOL

ATTN: BEN VALLES & AMY WHEELER

REGION 19 DISCOUNT PROVIDED IS 15%.  
Customer PO# QUOTE Phone 915-772-1469  
Order Status: Open Fax 915-779-2658

Item Name	Order	Sold	Due	Price	Ext Price	Tax
CLN-SW L CUSTOM LOUVERS CUSTOM LOUVERS FOR CHEMICAL ROOM OUTER. ALUMINUM ANODIZED COATING BEIGE, SIZE 21"X36". SET OF TWO.	1	0	1	\$3,819.90	\$3,819.90	N

LIST PRICE: \$4,494.00 MINUS 15% DISCOUNT EQUALS  
EXT PRICE OF \$3,819.90.

CLN-SW F CUSTOM DUCT CUSTOM STAINLESS STEEL 10" WIDE X 8" THICK X 98" DUCT. WITH INSTALLATION.	1	0	1	\$1,324.30	\$1,324.30	N
--	---	---	---	------------	------------	---

LIST PRICE: \$1,558.00 MINUS 15% DISCOUNT EQUALS  
EXT PRICE OF \$1,324.30.

CLN-CFYE FABENS POOL WORK	1	0	1	\$29,313.10	\$29,313.10	N
---------------------------	---	---	---	-------------	-------------	---

RE: FABENS POOL 526 NE G AVE. FABENS, TX 79838  
We make the following proposal:  
SCOPE OF WORK:  
-REMOVE POWER TO METER BY HAVING EL PASO  
ELECTRIC OPEN METER CAN. METER CAN SHOULD  
HAVE A BYPASS LEVER  
-REMOVE AND INSTALL NEW 100 AMP 240 VOLT NEMA  
3 MAIN LUG PANELBOARD. WITH BREAKERS AS PER  
EXISTING. RUN NEW CONDUIT. REPLACE CONDUIT  
AND WIRING FROM 100 AMP DISCONNECT TO NEW  
PANEL  
-REMOVE AND INSTALL NEW 3 PHASE 100 AMP 240  
VOLT NEMA 3 DISCONNECT WITH (3) 100 AMP FUSES  
-REMOVE AND INSTALL NEW 3 PHASE 60 AMP 240  
VOLT NEMA 3 DISCONNECT WITH (3) 40 AMP FUSES.  
REPLACE CONDUIT AND WIRING FROM 60 AMP  
DISCONNECT TO NEW SIZE 2 STARTER ENCLOSURE.  
-REMOVE AND INSTALL NEW 6X6X6 NEMA 3 GUTTER  
FOR SPLICING. SPLICE AS NEEDED  
-REMOVE AND INSTALL NEW SIZE 1 STARTER  
ENCLOSURE WITH (1) HAND OFF AUTO SWITCH AND  
(1)ON POSITION PILOT LIGHT FOR SLIDE MOTOR.  
REPLACE CONDUIT AND WIRING FROM GUTTER TO  
SIZE 1 STARTER ENCLOSURE  
-REMOVE AND INSTALL NEW SIZE 2 STARTER  
ENCLOSURE AND REPLACE CONDUIT FROM  
ENCLOSURE TO EXISTING SKIMMER MOTOR. MOTOR  
IS TO REMAIN. WILL DISCONNECT AND RECONNECT

3/4/2025  
Store: 1

Sales Order #8291  
Ordered: 3/4/2025  
Associate: Sysadmin  
Page 2

Item Name	Order	Sold	Due	Price	Ext Price	Tax
AS NEEDED -RUN NEW CONDUIT AND WIRING FOR NEW DCM 3 SERIES CONTROLLER AS PER SPECS PROVIDED. RUN NEW SEAL TIGHT WHIP AND CONNECT AS NEEDED -RUN NEW CONDUIT AND WIRING FOR WALL MOUNTED MOTOR WITH BOOSTER PUMP EXPANSION TANK. RUN NEW SEAL TIGHT WHIP AND CONNECT AS NEEDED -RUN NEW CONDUIT AND WIRING FOR (3) NEW QUADS ALONG EQUIPMENT SIDE WALL AS PER WALK THROUGH -REMOVE AND RUN NEW WIRING FOR (2) NEW WALL PACK STYLE LIGHT FIXTURES AS PER CUSTOMER REQUEST -REPLACE CONDUIT AND WIRING FOR CLOSET LIGHT AND SWITCH IN CHEMICAL ROOM IN FRONT OF BUILDING -INSTALL NEW DUPLEX RECEPTACLE IN CHEMICAL ROOM  INCLUDES: MATERIAL, LABOR AND PERMITS EXCLUDES: TROUBLESHOOTING EXISTING CIRCUITS, CONTROL BOXES, VALVE INSTALLS, NEW HOMERUNS EXCEPT FOR EXISTING ROTTED CONDUITS, CONTROLS AND PRESSURE SWITCHES, NEW DRIVES, PARAMETER SETTINGS, DATA CONDUITS, PLC'S, OVERTIME AND WEEKENDS, COMISSIONING, NEW MOTORS AND ANY UNFORESEEN ELECTRICAL WORK.  LIST PRICE: \$34,486.00 MINUS 15% DISCOUNT EQUALS EXT PRICE OF \$29,313.10.						
CLN ONSITE WORK	1	0	1	\$2,150.50	\$2,150.50	N
Total Qty Ordered: 4				0	4	
Percent Unfilled: 100						

Exempt	Subtotal:	\$36,607.80
	0 % Tax:	+ \$0.00
	<b>TOTAL:</b>	<b>\$36,607.80</b>
	<b>Deposit Balance:</b>	<b>\$0.00</b>
	Balance Due:	\$36,607.80

Please note this is a formal quotation for the items listed above and does not include any labor or material not shown.