

C.L. NORTH
C.L. North Pump Company
6820 Industrial Avenue
El Paso, TX, 79915
Phone # (915) 772-1469
Fax # (915) 779-2658
www.clnorth.com

Bill To: El Paso County Auditors Office
El Paso County Auditors Office
320 S.Campbell
El Paso, TX 79901
(915) 546-2040 ex 452

INSTRUCTIONS: REFERENCE REGION 19# 22-7434

FOR CANUTILLO POOL

ATTN: BEN VALLES & AMY WHEELER

REGION 19 DISCOUNT PROVIDED IS 15%.
Customer PO# QUOTE Phone 915-772-1469
Order Status: Open Fax 915-779-2658

Item Name	Order	Sold	Due	Price	Ext Price	Tax
CLN-SW L CUSTOM LOUVERS CUSTOM LOUVERS FOR CHEMICAL ROOM OUTER. ALUMINUM ANODIZED COATING BEIGE, SIZE 21"X36". SET OF TWO.	1	0	1	\$3,819.90	\$3,819.90	N

LIST PRICE: \$4,494.00 MINUS 15% DISCOUNT EQUALS
EXT PRICE OF \$3,819.90.

CLN-SW F CUSTOM DUCT CUSTOM STAINLESS STEEL 10" WIDE X 8" THICK X 98" DUCT. WITH INSTALLATION.	1	0	1	\$1,324.30	\$1,324.30	N
--	---	---	---	------------	------------	---

LIST PRICE: \$1,558.00 MINUS 15% DISCOUNT EQUALS
EXT PRICE OF \$1,324.30.

CLN-CCYE CANUTILLO POOL WORK RE: CANUTILLO POOL 7351 BOSQUE RD. CANUTILLO, TX 79835	1	0	1	\$29,313.10	\$29,313.10	N
---	---	---	---	-------------	-------------	---

We make the following proposal:
SCOPE OF WORK:
-REMOVE POWER TO METER BY HAVING EL PASO
ELECTRIC OPEN METER CAN. METER CAN SHOULD
HAVE A BYPASS LEVER
-REMOVE AND INSTALL NEW 100 AMP 240 VOLT NEMA
3 MAIN LUG PANELBOARD. WITH BREAKERS AS PER
EXISTING. RUN NEW CONDUIT. REPLACE CONDUIT
AND WIRING FROM 100 AMP DISCONNECT TO NEW
PANEL
-REMOVE AND INSTALL NEW 3 PHASE 100 AMP 240
VOLT NEMA 3 DISCONNECT WITH (3) 100 AMP FUSES
-REMOVE AND INSTALL NEW 3 PHASE 60 AMP 240
VOLT NEMA 3 DISCONNECT WITH (3) 40 AMP FUSES.
REPLACE CONDUIT AND WIRING FROM 60 AMP
DISCONNECT TO NEW SIZE 2 STARTER ENCLOSURE.
-REMOVE AND INSTALL NEW 6X6X6 NEMA 3 GUTTER
FOR SPLICING. SPLICE AS NEEDED
-REMOVE AND INSTALL NEW SIZE 1 STARTER
ENCLOSURE WITH (1) HAND OFF AUTO SWITCH AND
(1)ON POSITION PILOT LIGHT FOR SLIDE MOTOR.
REPLACE CONDUIT AND WIRING FROM GUTTER TO
SIZE 1 STARTER ENCLOSURE
-REMOVE AND INSTALL NEW SIZE 2 STARTER
ENCLOSURE AND REPLACE CONDUIT FROM
ENCLOSURE TO EXISTING SKIMMER MOTOR.

3/4/2025
Store: 1

Sales Order #8292
Ordered: 3/4/2025
Associate: Sysadmin
Page 2

Item Name	Order	Sold	Due	Price	Ext Price	Tax
MOTOR IS TO REMAIN. WILL DISCONNECT AND RECONNECT AS NEEDED -RUN NEW CONDUIT AND WIRING FOR NEW DCM 3 SERIES CONTROLLER AS PER SPECS PROVIDED. RUN NEW SEAL TIGHT WHIP AND CONNECT AS NEEDED -RUN NEW CONDUIT AND WIRING FOR WALL MOUNTED MOTOR WITH BOOSTER PUMP EXPANSION TANK. RUN NEW SEAL TIGHT WHIP AND CONNECT AS NEEDED -RUN NEW CONDUIT AND WIRING FOR (3) NEW QUADS ALONG EQUIPMENT SIDE WALL AS PER WALK THROUGH -REMOVE AND RUN NEW WIRING FOR (2) NEW WALL PACK STYLE LIGHT FIXTURES AS PER CUSTOMER REQUEST -REPLACE CONDUIT AND WIRING FOR CLOSET LIGHT AND SWITCH IN CHEMICAL ROOM IN FRONT OF BUILDING -INSTALL NEW DUPLEX RECEPTACLE IN CHEMICAL ROOM INCLUDES: MATERIAL, LABOR AND PERMITS EXCLUDES: TROUBLESHOOTING EXISTING CIRCUITS, CONTROL BOXES, VALVE INSTALLS, NEW HOMERUNS EXCEPT FOR EXISTING ROTTED CONDUITS, CONTROLS AND PRESSURE SWITCHES, NEW DRIVES, PARAMETER SETTINGS, DATA CONDUITS, PLC'S, OVERTIME AND WEEKENDS, COMISSIONING, NEW MOTORS AND ANY UNFORESEEN ELECTRICAL WORK LIST PRICE: \$34,486.00 MINUS 15% DISCOUNT EQUALS EXT PRICE OF \$29,313.10.						

CLN ONSITE WORK	1	0	1	\$2,150.50	\$2,150.50	T
Total Qty Ordered: 4				0	4	

Percent Unfilled: 100

Exempt	Subtotal:	\$36,607.80
	0 % Tax:	+ \$0.00
	TOTAL:	\$36,607.80
	Deposit Balance:	\$0.00
	Balance Due:	\$36,607.80

Please note this is a formal quotation for the items listed above and does not include any labor or material not shown.