



Proposal

Potential Change Order No.1, Revision 4 El Paso County Skate Parks

Date: Wednesday, January 15, 2025

Banes General Contractors, Inc
6001 Doniphan
El Paso, TX
Phone: (915) 584-0404
Fax: (915) 584-2432

To: **El Paso County**
800 East Overland, Suite 300
El Paso, TX 79901

Job	Vendor / Sub	Payment Terms	Due Date
El Paso County Skate Parks			

Proposal #	Description	Unit Price	Line Total
#1	4" Overlay above existing concrete slab - Estrella Park		\$ 41,166.00
#2	Additional sawcut and removal as per drawing issued by Architect		\$ 12,950.00
#3	4" Overlay above existing concrete slab - Gallegos Park		\$ 38,900.00
#4	Credit and Cost for Additional Work Requested by Owner		\$ (16,916.00)
			\$ -

Owner Signature for Execution

Name and Title

Subtotal	\$76,100.00
GC O/P (10%)	\$7,610.00
Total	\$83,710.00

EXHIBIT M



Ozaeta Construction LLC

October 4, 2024

El Paso County - Skate Parks Renovation (Estrella Park - Concrete Overlay) - Ozaeta Construction LLC is pleased to provide our proposal to furnish the necessary labor, material, and equipment required to complete the work for the above-referenced project. The following is our detailed scope of work, qualifications, and exclusions based on **Site Visit and Conversation with Bardo Contreras**. Our estimates are as follows:

El Paso County - Skate Parks Renovation	
Concrete	Total Price
<u>Estrella Skate Park - 14590 Greg Dr. El Paso, Texas 79938 (2" Concrete Overlay Reinf. W/Fiber)</u> ➤ 4,000 PSI - Reinf. W/Fiber (3lbs./yard) ➤ Sawcut, Demo, and remove concrete in a straight line. ***Exclude Subgrade, Select Fill, Dirt Work, and/or Basecourse. Done by Others. ***Exclude Epoxy Joint Filler Joint. Done by Others. ***Exclude Anchor Rods, Steel Plates, Galvanized Angles, Headed Studs, and Safety Guardrails. Done and Provided by Others. ***Exclude Warranty. Ozaeta Construction can not provide warranty for this work.	\$32,182.40
<u>Estrella Skate Park - 14590 Greg Dr. El Paso, Texas 79938 (4" Concrete Overlay)</u> ➤ 4,000 PSI - Reinf. W/W.W.F. (W2.9/W2.9) ➤ Sawcut, Demo, and remove concrete in a straight line. ***Exclude Subgrade, Select Fill, Dirt Work, and/or Basecourse. Done by Others. ***Exclude Epoxy Joint Filler Joint. Done by Others. ***Exclude Anchor Rods, Steel Plates, Galvanized Angles, Headed Studs, and Safety Guardrails. Done and Provided by Others. ***Exclude Warranty. Ozaeta Construction can not provide warranty for this work.	\$41,165.90
<u>Estrella Skate Park - 14590 Greg Dr. El Paso, Texas 79938 (4" Concrete Overlay - Over Prepared Subgrade)</u> ➤ 4,000 PSI - Reinf. W/W.W.F. (W2.9/W2.9) ➤ Sawcut, Demo, and remove concrete in a straight line. ➤ Remove and replace 6" of Existing Soil. Replace with 6" of TXDOT Base Course. Exclude Epoxy Joint Filler Joint. Done by Others. Exclude Anchor Rods, Steel Plates, Galvanized Angles, Headed Studs, and Safety Guardrails. Done and Provided by Others.	\$55,008.40

****Proposal Price is guaranteed for 30 days from the above date.**

****All work is based on a 40-hour-per-week schedule.**

****Exclude any other concrete work not mentioned above.**

****Exclude overall Joint Sealant, Stamped, Colored, or Artistic Concrete.**

QUALIFICATIONS:

- Safety for our scope of work.
- All concrete to be normal weight.
- General contractor to provide all temporary, utility, and sanitation facilities.
- Subgrade to be Received at 0.1' +/-
- OZ Construction shall place all concrete embeds, furnished by others.
- General Contractor to provide suitable benchmarks for use in layout concrete work.



Trade: Concrete
Sub's Name: Ozaeta Construction LLC
Project: El Paso County - Skate Parks Renovation
Date: 10/4/2024

Scope of Work Description:														
(Estrella Park) 4" Concrete Overlay - Requested by GC (Banes)														

Scope of Work Description	Materials					Units per MH	Labor			Equipment				Total Cost
	Item Description	UOM	Qty	Cost Per Unit	Total		MHRS	Rate	Total	Eq. Type	# Weeks	Rate	Total	
Concrete Work	Concrete (4,000 PSI)	EA.	100.0	\$155.00	\$15,500.00	Carpenter	40.00	19.00	\$760.00				\$0.00	\$16,260.00
	Wood Forms (2X12)	EA.	25.0	\$36.00	\$900.00	Carpenter	40.00	19.00	\$760.00				\$0.00	\$1,660.00
					\$0.00	Carpenter	40.00	22.00	\$880.00				\$0.00	\$880.00
					\$0.00	Finisher	40.00	22.00	\$880.00				\$0.00	\$880.00
					\$0.00	Finisher	40.00	22.00	\$880.00				\$0.00	\$880.00
					\$0.00	Finisher	40.00	22.00	\$880.00				\$0.00	\$880.00
					\$0.00	Skilled Labor	40.00	17.00	\$680.00				\$0.00	\$680.00
					\$0.00	Labor	40.00	15.00	\$600.00				\$0.00	\$600.00
					\$0.00	Labor	40.00	15.00	\$600.00				\$0.00	\$600.00
					\$0.00				\$0.00				\$0.00	\$0.00
Rebar/Wire Mesh	W.W.F. (W2.9 X W2.9)	EA	12.0	\$200.00	\$2,400.00	Rodbuster	24.00	23.00	\$552.00				\$0.00	\$2,952.00
					\$0.00	Rodbuster	24.00	23.00	\$552.00				\$0.00	\$552.00
					\$0.00	Rodbuster	24.00	23.00	\$552.00				\$0.00	\$552.00
					\$0.00	Labor	24.00	15.00	\$360.00				\$0.00	\$360.00
					\$0.00	Skilled Labor	40.00	17.00	\$680.00				\$0.00	\$680.00
					\$0.00	Labor	24.00	15.00	\$360.00				\$0.00	\$360.00
					\$0.00				\$0.00				\$0.00	\$0.00
Demolition Work					\$0.00	Saw Cutter	24.00	20.0	\$480.00	Husqvama FS 3500 E (SAW)	1.00	\$3,225.00	\$3,225.00	\$3,705.00
					\$0.00	Saw Cutter	24.00	20.0	\$480.00	Dieswl Gen. W00 KW	1.00	\$3,525.00	\$3,525.00	\$4,005.00
					\$0.00	Saw Cutter	24.00	20.0	\$480.00	Backhoe	1.00	\$2,800.00	\$2,800.00	\$3,280.00
					\$0.00	Skilled Labor	40.00	17.00	\$680.00				\$0.00	\$680.00
					\$0.00	Labor	24.00	15.0	\$360.00				\$0.00	\$360.00
					\$0.00	Labor	24.00	15.0	\$360.00				\$0.00	\$360.00
					\$0.00				\$0.00				\$0.00	\$0.00
Subtotals					\$18,800.00			396.0	\$12,816.00		3.0		\$9,550.00	\$41,166.00
					\$18,800.00			411.0	\$12,816.00		3.0		\$9,550.00	\$41,166.00
Total CO No. 1														



Ozaeta Construction LLC

January 10, 2025

El Paso County - Skate Parks Renovation (Gallegos Park – 4" Concrete Overlay) - Ozaeta Construction LLC is pleased to provide our proposal to furnish the necessary labor, material, and equipment required to complete the work for the above-referenced project. The following is our detailed scope of work, qualifications, and exclusions based on **Site Visit and Conversation with Bardo Contreras**. Our estimates are as follows:

<u>El Paso County - Skate Parks Renovation</u>	
<u>CO # 3 - 4" Concrete Overlay</u>	Total Price
<u>Gallegos Skate Park - 7361 Bosque Rd. Canutillo, TX 79835 (4" Concrete Overlay)</u> ➤ 4,000 PSI - Reinf. W/W.W.F. (W2.9/W2.9) - 12" Turn Downs at Edges. ➤ Sawcut, Demo, and remove concrete in a straight line. ➤ Additional Dowel Reinforcement needed where control Joints are at. ***Exclude Subgrade, Select Fill, Dirt Work, and/or Basecourse. Done by Others. ***Exclude Epoxy Joint Filler Joint. Done by Others. ***Exclude Anchor Rods, Steel Plates, Galvanized Angles, Headed Studs, and Safety Guardrails. Done and Provided by Others. ***Exclude Warranty. Ozaeta Construction can not provide warranty for this work.	\$38,900.00

****Proposal Price is guaranteed for 30 days from the above date.**

****All work is based on a 40-hour-per-week schedule.**

****Exclude any other concrete work not mentioned above.**

****Exclude overall Joint Sealant, Stamped, Colored, or Artistic Concrete.**

QUALIFICATIONS:

- Safety for our scope of work.
- All concrete to be normal weight.
- General contractor to provide all temporary, utility, and sanitation facilities.
- Subgrade to be Received at 0.1' +/-
- OZ Construction shall place all concrete embeds, furnished by others.
- General Contractor to provide suitable benchmarks for use in layout concrete work.

EXCLUSIONS:

- Undercutting of foundations and replacement with select material (engineered fill)
- Setting and filling of Pipe Bollards only. Pipe Bollard is to be supplied by a General Contractor.
- Steel Structures, steel plates, anchors, embedded plates, handrails, and/or any steel. (To be provided by General Contractors or Others)
- Furnishing of embedded and bolt-on metals. (Dock Angles to be supplied by the General Contractor.)
- Traffic control & barricades
- Performance and payment bonds
- Demolition, earthwork, utilities
- Waterproofing/Weatherproofing
- All items not specifically listed on this proposal.
- Architectural and decorative concrete
- Landscaping
- Materials testing
- General Contractor to provide any permits needed to perform the job.
- General Contractor to provide testing and any inspection needed to pour concrete.



Ozaeta Construction LLC

January 9, 2025

El Paso County - Skate Parks Renovation (CO #2 - Additional Saw Cutting and Replacement of Slab) - Ozaeta Construction LLC is pleased to provide our proposal to furnish the necessary labor, material, and equipment required to complete the work for the above-referenced project. The following is our detailed scope of work, qualifications, and exclusions based on **Site Visit and Conversation with Micheal Vasquez**. Our estimates are as follows:

El Paso County - Skate Parks Renovation	
CO #2 - Additional Saw Cutting and Replacement of Slab	Total Price
Agua Dulce Skate Park - Additional Areas Removed - Approx. 780 SF ➤ Sawcut, Demo, Remove and Haul Away Concrete Rubble ➤ 8" Slab with 12" Turn Down - Reinf. W/#3 Rebar @ 12" O.C.E.W. ➤ 4,000 PSI Concrete ***Exclude Subgrade, Select Fill, Dirt Work, and/or Basecourse. Done by Others. ***Exclude Epoxy Joint Filler Joint. Done by Others. ***Exclude Anchor Rods, Steel Plates, Galvanized Angles, Headed Studs, and Safety Guardrails. Done and Provided by Others. ***Exclude Warranty. Ozaeta Construction can not provide warranty for this work.	\$12,950.00

****Proposal Price is guaranteed for 30 days from the above date.**

****All work is based on a 40-hour-per-week schedule.**

****Exclude any other concrete work not mentioned above.**

****Exclude overall Joint Sealant, Stamped, Colored, or Artistic Concrete.**

QUALIFICATIONS:

- Safety for our scope of work.
- All concrete to be normal weight.
- General contractor to provide all temporary, utility, and sanitation facilities.
- Subgrade to be Received at 0.1' +/-
- OZ Construction shall place all concrete embeds, furnished by others.
- General Contractor to provide suitable benchmarks for use in layout concrete work.

EXCLUSIONS:



Date	1/15/2025
To	Banes General Contractors Inc

Phone:	915-584-0404
Email:	bardo@banes-gc.com
Email Only	X
Fax & Email	

Project Name:	El Paso County Skate Parks Renovations
---------------	--

This agreement confirms our discussion regarding the services as described herein. The following services have been provided upon receipt of this signed agreement. These services will be identified on your billing by the Task Name assigned below.


Task Name:	Additional Services - Flatwork
------------	--------------------------------

Item#	Qty	Unit	Description	Unit \$	Total
ESTRELLA					\$ -
Foam	1	LS	Addtl foam due to 4 inch elevation change (material only)	\$ 4,679.40	\$ 4,679.40
Concrete	1	LS	Addtl concrete at toe and on edges above walls due to 4 inch elevation change	\$ 3,045.00	\$ 3,045.00
Form work	1	LS	form work at bottom of all features	\$ 6,925.00	\$ 6,925.00
Credit	1	LS	Concrete slab repair	\$ (12,500.00)	\$ (12,500.00)
Credit	1	LS	Concrete flat work refill	\$ (17,500.00)	\$ (17,500.00)
AGUA DULCE					\$ -
Concrete	1	LS	Provide Additional 14' steel and concrete Curb Feature	\$ 3,650.00	\$ 3,650.00
GALLEGOS					\$ -
Foam	1	LS	Addtl foam due to 4 inch elevation change (Material, Dellivery and Labor)	\$ 5,350.00	\$ 5,350.00
Concrete	1	LS	Addtl concrete at toe and on edges due to 4 inch elevation change	\$ 2,001.00	\$ 2,001.00
Form work	1	LS	Form work at bottom of all features (Material, Dellivery and Labor)	\$ 6,813.00	\$ 6,813.00
Concrete	1	LS	Assistance / Quality Review / Tools	\$ 2,000.00	\$ 2,000.00
Credit	1	LS	Concrete flat work Repair	\$ (16,700.00)	\$ (16,700.00)
					\$ (16,916.00)

Impact on Schedule:	3 weeks Estrella, 2 Days Agua Dulce, 2 weeks Gallegos	Type of Billing	Design, Materials and Labor
		Total	\$ (16,916.00)

If this meets with your approval, please sign in the spave provided below and return so that these services may be scheduled. Please keep a copy for your records.

Hardcore Skateparks

Signature 

By: William D. Minadeo III

Title: President

Date: 1/15/2025

Client Approval

Signature _____

By: _____

Title: _____

Date: _____